


Description	Commercial	Residential	 IRONWORKS MANUFACTURING & SUPPLY	Style
	Vertical Picket	3/4" Pre-Galvanized Square Steel Tube 18 Gauge Thickness		5/8" Pre-Galvanized Square Steel Tube 18 Gauge Thickness
Horizontal Rail	1-1/4" Pre-Galvanized Square Steel Tube 14 Gauge Thickness	1-1/4" Pre-Galvanized Square Steel Tube 14 Gauge Thickness		
Post	2-1/2" Pre-Galvanized Square Steel Tube 14 Gauge	2" Pre-Galvanized Square Steel Tube 14 Gauge		
Post Cap	Die Cast Zinc or Polymer Materials Available	Die Cast Zinc or Polymer Materials Available		
Finial	Die Cast Zinc or Polymer Materials Available	Pressed Point		
	Size Specifications: Installed Height 4, 5, 6, and 8 foot Heights Panel Length 93-1/8 Inches Picket Spacing 6" or 4.5" on Center	Size Specifications: Installed Height 4, 5, and 6 foot Heights Panel Length 93-1/8 Inches Picket Spacing 6" or 4" on Center		